


10/510696
18 03 / 1342



**WORLD INTELLECTUAL PROPERTY ORGANIZATION
ORGANISATION MONDIALE DE LA PROPRIÉTÉ INTELLECTUELLE**

34, chemin des Colombettes, Case postale 18, CH-1211 Genève 20 (Suisse)
Téléphone: (41 22) 338 91 11 - e-mail: wipo.mail@wipo.int - Fac-similé: (41 22) 733 54 28

**PATENT COOPERATION TREATY (PCT)
TRAITÉ DE COOPÉRATION EN MATIÈRE DE BREVETS (PCT)**

**CERTIFIED COPY OF THE INTERNATIONAL APPLICATION AS FILED
AND OF ANY CORRECTIONS THERETO**

**COPIE CERTIFIÉE CONFORME DE LA DEMANDE INTERNATIONALE, TELLE QU'ELLE
A ÉTÉ DÉPOSÉE, AINSI QUE DE TOUTES CORRECTIONS Y RELATIVES**

International Application No. } **PCT/IB02/01181**
Demande internationale n° }


International Filing Date } **12 April 2002**
Date du dépôt international } **(12.04.02)**

Geneva/Genève,
01 May 2003
(01.05.03)

**International Bureau of the
World Intellectual Property Organization (WIPO)**

**Bureau International de l'Organisation Mondiale
de la Propriété Intellectuelle (OMPI)**

PRIORITY DOCUMENT
SUBMITTED OR TRANSMITTED IN
COMPLIANCE WITH
RULE 17.1(a) OR (b)



J.-L. Baron

**Head, PCT Receiving Office Section
Chef de la section "office récepteur du PCT"**

PCT REQUEST

Original (for SUBMISSION) - printed on 12.04.2002 09:25:57 AM

0	For receiving Office use only	
0-1	International Application No.	PCT / IB 0 2 / 0 1 1 8 1
0-2	International Filing Date	12 APRIL 2002 (12.04.02)
0-3	Name of receiving Office and "PCT International Application"	INTERNATIONAL BUREAU OF WIPO PCT International Application
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	PCT-EASY Version 2.92 (updated 01.01.2002)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	International Bureau of the World Intellectual Property Organization (RO/IB)
0-7	Applicant's or agent's file reference	WO31010
I	Title of invention	SYSTEM, DEVICE AND METHOD FOR IMPROVING THROUGHPUT IN A COMMUNICATION NETWORK, PREFERABLY A MOBILE IPv6-BASED NETWORK
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	NOKIA CORPORATION
II-5	Address:	Keilalahdentie 4 FIN-02150 Espoo Finland
II-6	State of nationality	FI
II-7	State of residence	FI
II-8	Telephone No.	+358 9 1807 0
II-9	Facsimile No.	+358 9 1807 496
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	ZHANG, Dongmei
III-1-5	Address:	Building 10, Room 433 Longziang Road, Haidian District Beijing China
III-1-6	State of nationality	CN
III-1-7	State of residence	CN

(Einschreibungsdatum 12.04.02 PCT - Ann.)

PCT REQUEST

WO31010

Original (for SUBMISSION) - printed on 12.04.2002 09:25:57 AM

III-2	Applicant and/or inventor	
III-2-1	This person is:	applicant and inventor
III-2-2	Applicant for	US only
III-2-4	Name (LAST, First)	ZHANG , Runtong
III-2-5	Address:	c/o NOKIA CORPORATION Keilalahdentie 4 FIN-02150 Espoo Finland
III-2-6	State of nationality	CN
III-2-7	State of residence	FI
III-3	Applicant and/or inventor	
III-3-1	This person is:	applicant and inventor
III-3-2	Applicant for	US only
III-3-4	Name (LAST, First)	KAN , Zhigang
III-3-5	Address:	c/o NOKIA CORPORATION Keilalahdentie 4 FIN-02150 Espoo Finland
III-3-6	State of nationality	CN
III-3-7	State of residence	FI
III-4	Applicant and/or inventor	
III-4-1	This person is:	applicant and inventor
III-4-2	Applicant for	US only
III-4-4	Name (LAST, First)	MA, Jian
III-4-5	Address:	c/o NOKIA CORPORATION Keilalahdentie 4 FIN-02150 Espoo Finland
III-4-6	State of nationality	FI
III-4-7	State of residence	FI
IV-1	Agent or common representative; or address for correspondence	
	The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name (LAST, First)	BÖCKELEN, Rainer
IV-1-2	Address:	Tiedtke-Bühling-Kinne Bavariaring 4 D-80336 Munich Germany
IV-1-3	Telephone No.	+49 89 54 46 90
IV-1-4	Facsimile No.	+49 89 53 26 11
IV-1-5	e-mail	postoffice@tbk-patent.de

PCT REQUEST

WO31010


Original (for SUBMISSION) - printed on 12.04.2002 09:25:57 AM

IV-2	Additional agent(s)	additional agent(s) with same address as first named agent
IV-2-1	Name(s)	TIEDTKE, Harro; KINNE, Reinhard; PELLMANN, Hans-Bernd; GRAMS, Klaus; VOLLNHALS, Aurel; LESON, Thomas, Johannes, Alois; CHIVAROV, Georgi; GRILL, Matthias; KÜHN, Alexander; KLINGELE, Stefan; ROTH, Ronald
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: GH GM KE LS MW MZ SD SL SZ TZ UG ZM ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE CH&LI CY DE DK ES FI FR GB GR IE IT LU MC NL PT SE TR and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GQ GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT
V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AG AL AM AT AU AZ BA BB BG BR BY BZ CA CH&LI CN CO CR CU CZ DE DK DM DZ EC EE ES FI GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX MZ NO NZ OM PH PL PT RO RU SD SE SG SI SK SL TJ TM TN TR TT TZ UA UG US UZ VN YU ZA ZM ZW
V-5	Precautionary Designation Statement In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.	
V-6	Exclusion(s) from precautionary designations	NONE
VI	Priority claim	NONE
VII-1	International Searching Authority Chosen	European Patent Office (EPO) (ISA/EP)

PCT REQUEST

WO31010

Original (for SUBMISSION) - printed on 12.04.2002 09:25:57 AM

VIII	Declarations	Number of declarations	
VIII-1	Declaration as to the identity of the inventor	-	
VIII-2	Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent	-	
VIII-3	Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application	-	
VIII-4	Declaration of inventorship (only for the purposes of the designation of the United States of America)	-	
VIII-5	Declaration as to non-prejudicial disclosures or exceptions to lack of novelty	-	
IX	Check list	number of sheets	electronic file(s) attached
IX-1	Request (including declaration sheets)	5	-
IX-2	Description	15	-
IX-3	Claims	4	-
IX-4	Abstract	1	EZABST00.TXT
IX-5	Drawings	3	-
IX-7	TOTAL	28	
	Accompanying items	paper document(s) attached	electronic file(s) attached
IX-8	Fee calculation sheet	✓	-
IX-11	Copy of general power of attorney	✓	-
IX-17	PCT-EASY diskette	-	Diskette
IX-19	Figure of the drawings which should accompany the abstract	2	
IX-20	Language of filing of the international application	English	
X-1	Signature of applicant, agent or common representative		
X-1-1	Name (LAST, First)	BÖCKELEN, Rainer	

FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	12 APRIL 2002	(12.04.02)
10-2	Drawings:		
10-2-1	Received		
10-2-2	Not received		
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application		
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)		
10-5	International Searching Authority	ISA/EP	
10-6	Transmittal of search copy delayed until search fee is paid		

5/5

PCT REQUEST

WO31010

Original (for SUBMISSION) - printed on 12.04.2002 09:25:57 AM

FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	---	--

TITLE

SYSTEM, DEVICE AND METHOD FOR IMPROVING THROUGHPUT
IN A COMMUNICATION NETWORK, PREFERABLY A
MOBILE IPv6-BASED NETWORK

DESCRIPTION

FIELD AND BACKGROUND OF THE INVENTION

The invention relates to a method and system for improving throughput in a communication network, preferably a Mobile IPv6-based network. IPv6 stands for the Internet Protocol version 6 (as compared to the existing IPv4) and is a standardized protocol. Mobile IPv6 is a standardized protocol which supports mobility in IPv6.

In particular, the present invention is related to a method and system to improve TCP performance, especially the throughput of TCP connection and utilization of the network resource, when a mobile node in the Mobile IPv6 network hands over between two subnets.

TCP (Transmission Control Protocol) is a reliable transport protocol that has been tuned for networks composed of wired links and stationary hosts. It interprets an unexpected increase in delay as packet losses caused by congestion. The congestion control policies have been proved beneficial in improving the overall performance of the networks like the current Internet.

Mobile IPv6 networks, however, will include wireless links and mobile hosts. In Mobile IPv6, a mobile node (MN) is

always addressable by its home address, whether it is currently attached to its home link or is away from home. While a mobile node is attached to some foreign link away from home, it is also addressable by one or more care-of addresses, in addition to its home address. Correspondent node (CN) is any node communicating with mobile node. After the mobile node acquires its care-of address in a foreign link, it will register the association between the mobile node's home address and this care-of address with home agent and correspondent node by sending a packet containing a "Binding Update" destination option, as shown in Fig. 1.

When TCP is used as the transport protocol, some types of delay and packet loss that are unrelated to congestion will be encountered during mobile node handing over between two subnets. The problem with existing TCP is that the packets lost during handoff are interpreted as network congestion. In more detail, the typical congestion control mechanisms will misinterpret unexpected increase in delay as packet losses caused by congestion, and may degrade the network performance because the congestion state is followed automatically by the TCP slow start procedure.

In Mobile IPv6, there are several types of delay and loss that are unrelated to congestion. First, communications may slow down while the handovers between two subnets occur, packets cannot again be routed to and from the mobile node until the handover completes. Second, packets may be lost due to the relatively frequent transmission errors suffered by wireless link. Third, packets may be lost due to the limited buffer in home agent buffering packets when a mobile node is attached to some foreign link away from home.

When these unexpected delays due to handover happen, the typical TCP congestion control will interpret it as network

congestion. Therefore, the congestion window shrinks to its minimum value (one segment) abruptly and begins to invoke the slow-start algorithm till an acknowledgment (ACK) reaches TCP transmitter. As ACK reach the TCP transmitter (CN), slow-
5 start algorithm begins to grow the congestion window exponentially until it reaches a threshold, then grows it linearly. The threshold is set to one half of the window size at the time of the retransmission timeout. After handover completes for long time, the congestion window returns
10 gradually to its previous level before the window shrinks, as shown in Fig 3 by broken lines.

Actually, the slow start algorithm is effective when network congestions are indeed detected. However in the handover
15 scenario, slow start usually is not triggered by network congestions, but by handovers. Hence, the slow recovery of the congestion window due to slow start algorithm after each handover causes to the losses of throughput.

20 In Mobile IPv6, a handover of a mobile node between two subnets will degrade TCP performance, especially throughput and utilization of network resource.

Because of the key roles of TCP in the Internet, through
25 these years, various attempts have been made to enhance TCP functions. Recently, along with the rapidly development of satellite or mobile technologies, improving TCP's performance on wireless links has been becoming a challenge and an active research topic.

30

In wired link scenarios, there are many TCP enhancement methods, which are well applied. Among all the amendments to TCP, slow start, congestion avoidance, fast retransmission and fast recovery have been proven very efficient and mature,
35 and well applied. Another example is the Explicit Congestion

Notification (ECN). Fast-TCP has recently proposed, and its control philosophy is different from all previous methods. However, some problems still exist when these methods are used in wireless environment.

5

Regarding the TCP enhancements on the wireless platform, considerable efforts are devoted to determining the cause of packet drops and accordingly taking control actions.

Generally, forward error correction (FEC), automatic repeat request (ARQ), indirect TCP (I-TCP), snoop, explicit loss notification (ELC), selective ACK (SACK), forward ACK (FACK), new ECN, and Full Rate (FR+) are some possible solutions in this category.

15

SUMMARY OF THE INVENTION

The invention aims, among others, to improve performance, e.g. to provide TCP enhancements for solving handover-related problems.

20

The present invention provides a method, system and device as defined in the independent claims or any one of the dependent claims.

25

The invention preferably relates to IPv6 mobility and TCP optimization methods "fast retransmit" and "fast recovery". In fast retransmit method lost packets are detected in TCP transmitter by means of three or more duplicate ACKs.

30

The invention further preferably relates to IPv6 handoff between two subnets.

The invention provides a method and system for improving throughput in a communication network, preferably a Mobile

35

IPv6-based network.

In accordance with one of the aspects of the invention, the invention relates to a case where e.g. CN is taken as the TCP
5 transmitter and MN as the TCP receiver.

According to one of the aspects of the invention, when a mobile node after the handoff and address autoconfiguration in the new subnet sends a binding update message towards the
10 correspondent node, the binding update is interpreted as a signal to the TCP layer. The signal indicates to the TCP layer that fast recovery procedures should be initiated, instead of slow start. The signal can be implemented as duplicating ACK packets by the IP layer to the TCP layer.

15

One of the objective of the present invention is to provide a method for triggering the fast retransmit and fast recovery mechanism as fast as possible, by means of which the throughput of TCP connection and the utilization of the
20 network resource can be improved.

The objective is achieved by a method, which, according to one of the embodiments, comprises the following steps:

- 1) When a mobile node moves from one subnet into another
25 foreign subnet, it acquires its care-of address in foreign link, e.g. according to the methods of IPv6 Neighbor Discovery;
- 2) the mobile node registers the association between the mobile node's home address and this care-of address with home
30 agent and correspondent node by sending a packet containing a "Binding Update" destination option;
- 3) when the correspondent node receives the packet containing the "Binding Update", the Mobile IPv6 software in the correspondent node signals the TCP software;
- 35 4) the TCP software on correspondent node invokes the fast

retransmit and fast recovery mechanism when it receives the signal from the Mobile IPv6 software.

An advantage of the invention is to invoke fast retransmit
5 and fast recovery mechanism other than slow start mechanism after handover completing, so as to improve TCP performance, especially throughput. Fast retransmit and fast recovery algorithms are known TCP congestion control methods. The idea is that if three or more duplicate ACKs are received by a TCP
10 transmitter, the missing segment will be retransmitted immediately, without waiting for the retransmission timer to expire. Then instead of performing slow-start algorithm, congestion avoidance algorithm is invoked. Invoking fast retransmit and fast recovery algorithms other than slow start
15 will improve throughput of TCP connection.

Another advantage of the invention is that there is one trigger mechanism to invoke fast retransmit and fast recovery algorithms. In Mobile IPv6, fast retransmit and fast recovery
20 algorithms could not be triggered automatically immediately after completion of handovers because ACKs could not be sent until the handover completed. The invention thus provides a trigger to fast retransmit and fast recovery algorithms.

25 A further advantage of the invention is the ability to trigger fast retransmit and fast recovery algorithms as soon as possible. In Mobile IPv6, after the mobile node acquires its care-of address in foreign link, it will register this care-of address with home agent and correspondent node by
30 sending the "Binding Update" destination option. The "Binding Update" destination option is the earliest signal for the correspondent node to be informed that the handover is successful and will be completed soon. Hence, it is the earliest time for correspondent node to trigger fast
35 retransmit and fast recovery algorithms.

There are key features, either to be provided isolated or in any arbitrary combination, of the present invention which improve earlier solutions: Invocation of fast retransmit and fast recovery mechanism other than slow start mechanism after handover completion; one trigger mechanism to invoke fast retransmit and fast recovery algorithms; triggering fast retransmit and fast recovery algorithms as fast as possible.

Some of the provided advantages are: Improvement of the TCP performance, e.g of TCP throughput; Improvement of the utilization of network resource; Only minor modifications to the TCP and Mobile IPv6 software in TCP transmitter are be made.

BRIEF DESCRIPTION OF THE DRAWINGS

Fig 1 illustrates an embodiment of the invention and illustrates a basic relation between Mobile Node (MN) and Correspondent Node (CN), for initializing a "Binding Update" destination option;

Fig 2 shows a time scale for comparing flow charts of an embodiment of a method in accordance with the invention, and of a method not using the embodiment of the invention; and

Fig 3 shows a comparison of the behavior of a congestion window in response to handover with and without an embodiment of the method in accordance with the invention.

DETAILED DESCRIPTION OF PREFERRED EMBODIMENTS OF THE INVENTION

The invention can be implemented e.g. in a TCP sender with

small modifications. TCP sender can be any mobile equipments, such as mobile phones, Personal Digital Assistants (PDAs), laptops, which have e.g. mobile IPv6 stack.

- 5 Fig 1 illustrates a first embodiment of a communication system in accordance with the present invention and shows a mobile IPv6 basic operation. A Mobile Node (MN) 1 is represented two times, once attached to its home link (upper position of Fig. 1), and once after moving to another
10 location (lower position of Fig. 1) where the MN 1 is away from home and attached not to its home link but served by another serving entity, i.e. by a foreign link. A Home Agent (HA) 2 is associated to the MN for traffic control. With a Mobile IPv6 Binding Update (BU) message, a remote node such
15 as the MN 1 after moving, may inform any other node such as the HA 2 that all traffic sent to the remote node's home address should be currently sent to another address, the so called care-of-address.
- 20 The Mobile Node (MN) 1 detects his movement e.g. by receiving a Routing advertisement from a router, and generates his Care-of-Address (COA) with a stateless or a stateful address allocating procedure. MN 1 sends this information to his Home Agent (HA) 2 by a Binding Update (BU) message. HA 2 modifies
25 the information on the address entry in its Binding Cache and e.g. returns a Binding Acknowledgement (BAck) message to MN 1.

30 Packets from a Correspondent Node (CN) 7 or any other node to the shadow of the Home Address of MN 1 are blocked by the HA 2 and are tunneled to the MN 1 for the destination in the Binding Cache. The connection and traffic between MN 1, HA 2, and CN 7, is effected via the internet 6. The Binding Update message is represented by reference numeral 5. The connection
35 between MN 1 and CN 7 is represented by link 3. Link 4

represents any connection between MN 1 and any other node handled via internet 6.

Fig. 2 shows flow charts with a time scale for comparing the previous method and the method/system according to the invention. The time axis is shown at the right-hand side of Fig. 2. The left column S_A represents the IP layer in the MN 1. The middle column S_B shows the normal previous behaviour of CN 7 when not employing the method according to the invention.

The right-hand column S_C shows the behaviour of CN 7 when employing the method according to the invention.

- 15 In step S1 it is assumed that the MN 1 moves into a foreign subnet. In step S2, the MN 1 acquires a new care-of address (CoA), and sends, in step S3, a binding update message to HA 2 and/or CN 7.
- 20 In step S4 of the middle column S_B showing the normal previous behaviour of CN 7, CN 7 receives the Binding Update message either directly from MN 1, or from HA 2, but does nothing to TCP.
- 25 In step S5, it is assumed that the CN 7 sends data and waits for an Acknowledgment message ACK confirming receipt of the sent data. At step S6, TCP Timeout is checked as usual. Due to the handover, some packets will get lost so that the ACKs are not properly returned. As long as TCP has not timed out,
- 30 the waiting loop is executed via steps S6, S7, "Waiting", for the set waiting period. After TCP timeout, the answer of checking step S6 is "Yes" and the program proceeds to step S8, i.e. to the customary slow start mechanism wherein the size of the congestion window cwnd is set to 1 (cwnd=1). In
- 35 step S9, the congestion window is slowly returned to the

previous value before handover, by increasing the size of the congestion window by "1" for each received ACK message.

- Now, the right-hand column S_c showing the behaviour of CN 7 when employing the method according to the invention is considered. In step S10, the CN 7 receives the Binding Update message, and then informs its TCP software/structure thereon (step S11). The TCP software responds by executing step S12, i.e. it triggers its fast retransmit & fast recovery mechanism. Thus, the CN 7 does not wait for TCP timeout but immediately starts the fast retransmit/recovery mechanism for bringing back the congestion window to its value before the handover as quickly as possible.
- In step S13, the congestion window thus returns to the value before handover very fast.

Fig 3 shows a comparison of the behavior of the congestion window in response to handover with and without employing the method according to the invention. The solid line illustrates the behavior of the congestion window in response to handover when employing the method according to the invention, i.e. when triggering the fast retransmit & fast recovery after handover detection.

The broken line of Fig. 3 shows the behavior of the congestion window in response to handover when not using the method according to the invention, i.e when employing the slow start process. The X axis represents time, the Y axis the congestion window size and thus TCP throughput.

The handover occurrences are illustrated by dot-and-dash lines. As shown in Fig. 3, the method according to the invention provides a very fast growth of the congestion window size and thus system performance and throughput, in a

step- and subsequent ramp-like fashion, after any handover occurrence.

Contrary thereto, the growth of the congestion window size as well as momentary window size, and thus system performance and throughput, is much slower with the conventional slow start technique after handover, as shown by the broken line in Fig. 3.

10 When the binding updates to the correspondent node should be handled by an agent acting on behalf of the correspondent node, the agent is preferably programmed to send either the binding update messages, or a command for starting the fast retransmit & fast recovery, to the correspondent node, i.e. to the TCP transmitter.

According to another embodiment, the CN is adapted to check, when it receives a Binding Update message, whether it has sent any not yet acknowledged data, i.e. it is waiting for acknowledgment messages, or whether it has any data to be sent actually. When the CN does not have any unacknowledged data, i.e. it is not waiting for acknowledgment messages, or does presently not intend to send any data, the correspondent node may be programmed simply not to do anything special if it gets a Binding Update message. When the check should however reveal that the CN has sent any not yet acknowledged data, i.e. it is waiting for acknowledgment messages, or intends to send any data, the above mentioned fast retransmit & fast recovery method of the correspondent node is triggered.

The functioning of the method and system according to the invention can be tested by pretending to lose one or more packets, and checking the actions taken by the correspondent node when it gets a Binding Update message.

Buffer management (BM) might cause duplication of packets which can be dealt with in the MN, but wastes radio resources. An option is to agree between the MN and the CN upon the use of the disclosed method. This can bypass problems with BM and hierarchic mobility management.

The present invention thus provides a method for improving TCP performance, especially throughput and utilization of network resource.

In the following, some basic explanations on the algorithms mentioned above are given with reference to RFC 2001.

15 Slow Start Algorithm:

The slow start algorithm adds another window to the sender's TCP: the congestion window "cwnd", so as to allow the rate of injecting new packets into the network to be the rate of returning acknowledgments by the other end.

20

When a new connection is established with a host on another network, the congestion window is initialized to one segment. Each time an ACK is received, the congestion window is increased by one segment. The sender can transmit packets up to the minimum of the congestion window and the advertised window. The congestion window provides flow control imposed by the sender, while the advertised window is a flow control imposed by the receiver. The sender flow control is based on the sender's assessment of perceived network congestion.

30

The sender starts by transmitting one segment and waiting for its ACK. When that ACK is received, the congestion window is incremented to two so that two segments can be sent. When each of those two segments is acknowledged, the congestion window is increased to four, providing approximately

exponential growth. When the capacity of the network is reached, packets may be lost. This informs the sender that its congestion window has grown too large.

5 Congestion Avoidance:

Congestion avoidance deals with lost packets. Congestion can e.g. occur when high data rate input streams arrive at a router with insufficient output capacity. A loss of a packet signals congestion somewhere in the network between the
10 source and destination. There are two possible indications of packet loss: occurrence of timeout, or receipt of duplicate ACKs. When congestion occurs TCP slows down its transmission rate of packets into the network, and invokes the slow start algorithm.

15

Congestion avoidance and slow start require that two variables be maintained for each connection: a congestion window, cwnd, and a slow start threshold size. Slow start continues until TCP is halfway to where it was when
20 congestion occurred, and then congestion avoidance takes over. Congestion avoidance dictates that cwnd be incremented each time an ACK is received, with linear growth of cwnd.

3. Fast Retransmit:

25 The Fast Retransmit algorithm is a modification to the congestion avoidance algorithm. Note that TCP may generate an immediate acknowledgment (a duplicate ACK) when an out-of-order segment is received. This duplicate ACK should not be delayed. This duplicate ACK informs the other node that a
30 segment was received out of order.

Since TCP does not know whether a duplicate ACK is caused by a lost segment or just a reordering of segments, it waits for a small number of duplicate ACKs to be received. If there is
35 just a reordering of the segments, there will be only one or

two duplicate ACKs before the reordered segment is processed, which will then generate a new ACK. If three or more duplicate ACKs are received in a row, this will normally be caused by having lost a segment during transmission. TCP then performs a retransmission of the missing unacknowledged segment, without waiting for a retransmission timer to expire.

4. Fast Recovery

After fast retransmit has resend the missing segment, congestion avoidance (not slow start) is performed. This is the fast recovery algorithm. It is an improvement that allows high throughput under moderate congestion, especially for large windows.

The fast retransmit and fast recovery algorithms are usually implemented together as follows.

1. When the third duplicate ACK is received in succession, the slow start threshold size sst is set e.g. to one-half of the current congestion window, cwnd, and the missing segment is retransmitted. Then, cwnd is set to sst plus 3 times the segment size. This increases the congestion window by the number of segments received by the other end.

2. Each time another duplicate ACK arrives, cwnd is incremented by the segment size, so as to increase the congestion window each time an additional segment has left the network.

3. When a next ACK arrives that acknowledges new data, this ACK will normally be the acknowledgment of the retransmission performed in step 1. This ACK acknowledges all the intermediate segments sent between the lost packet and the receipt of the first duplicate ACK. The cwnd is then set to sst, e.g. to the value of sst set in step 1. This step provides congestion avoidance, since TCP is reduced to one-half of the rate before losing the packet.

Although the invention has been described above with reference to specific embodiments, the scope of the invention also covers any alterations, additions, modifications, and
5 omissions of the disclosed features.

CLAIMS

5

1. Method for managing a communication between a first network element and a second network element, wherein the communication is performed via a network on a packet-switched basis with acknowledgment messages acknowledging receipt of packets being returned to the packet sending network element, and a congestion control being performed wherein the number of packets being allowed to be sent before receipt of acknowledgment messages for these packets depends on the receipt of acknowledgment messages,

15 wherein, when the first network element performs a hand-over and sends a message informing the network on the hand-over, the network changes the congestion control to provide faster recovery rate after packet loss as compared to the normal recovery rate after packet loss.

20

2. Method according to claim 1, wherein the first network element is a mobile node which, when moving from one subnet into another foreign subnet, acquires a care-of address, and sends the message, preferably a "Binding Update" message, to its home network informing the latter on the care-of-address.

25

3. Method according to claim 1 or 2, wherein the message is sent to the second network element which, when receiving the message, triggers the invocation of a fast retransmit and fast recovery algorithm.

30

4. Method according to any one of the preceding claims, wherein the second network element is a correspondent node.

35

5. Method according to claim 4, wherein the second network element, when receiving the message, informs its TCP software, preferably its Mobile IPv6 software, which in response triggers the invocation of a fast retransmit and fast recovery algorithm.

6. Method according to any one of the preceding claims, wherein the communication between the first and second network elements is an IPv6-based communication.

7. Method according to any one of the preceding claims, wherein the message is interpreted as a signal to a TCP layer, the signal indicating to the TCP layer that fast recovery procedure is to be initiated.

8. Method according to claim 7, wherein the signal is implemented by duplicating ACK packets by an IP layer to the TCP layer.

9. Method according to any one of the preceding claims, wherein the faster recovery rate is implemented by increasing the size of a congestion window to an intermediate value in a one-step-manner, and by subsequent ramp-like increase of the congestion window size.

10. System for managing a communication between a first network element and a second network element, wherein the communication is performed via a network on a packet-switched basis with acknowledgment messages acknowledging receipt of packets being returned to the packet sending network element, comprising a congestion control for controlling the number of packets being allowed to be sent before receipt of acknowledgment messages for these packets, the congestion control being adapted to, when the first network element performs a hand-over and sends a message

informing the network on the hand-over, change so as to provide faster recovery rate after packet loss as compared to the normal recovery rate after packet loss.

5 11. System according to claim 10, wherein the first network element is a mobile node which is adapted, when moving from one subnet into another foreign subnet, to acquire a care-of address, and to send the message, preferably a "Binding Update" message, to its home network
10 informing the latter on the care-of-address.

12. System according to claim 10 or 11, wherein the second network element is adapted, when receiving the message, to trigger the invocation of a fast retransmit and
15 fast recovery algorithm.

13. System according to any one of the preceding system claims, wherein the second network element is a correspondent node.
20

14. System according to any one of the preceding system claims, wherein the second network element is adapted, when receiving the message, to inform its TCP software, preferably its Mobile IPv6 software, which in response triggers the
25 invocation of a fast retransmit and fast recovery algorithm.

15. System according to any one of the preceding system claims, wherein the communication between the first and second network elements is an IPv6-based communication.
30

16. System according to any one of the preceding system claims, wherein the congestion control is adapted to convert the message to a signal to a TCP layer, the signal indicating to the TCP layer that fast recovery procedure is to be
35 initiated.

17. System according to claim 16, wherein an IP layer of the second network element is implemented to generate the signal by duplicating ACK packets to the TCP layer.

5


18. System according to any one of the preceding system claims, wherein the congestion control is adapted to provide the faster recovery rate by increasing the size of a congestion window to an intermediate value in a one-step-
10 manner, and by subsequent ramp-like increase of the congestion window size.

ABSTRACT


5

The invention relates to a method and system for managing a communication between a first mobile network element and a second network element, wherein the communication is performed via a network on a packet-switched basis with acknowledgment messages acknowledging receipt of packets being returned to the packet sending network element. A congestion control is provided for controlling the number of packets being allowed to be sent before receipt of acknowledgment messages for these packets. The congestion control is adapted to, when the first network element performs a hand-over and sends a message informing the network on the hand-over, change so as to provide faster recovery rate after packet loss as compared to the normal recovery rate after packet loss. The mobile network element is adapted, when moving from one subnet into another foreign subnet, to acquire a care-of address, and to send the message, preferably a "Binding Update" message, to its home network informing the latter on the care-of-address. The second network element is adapted, when receiving the message, to trigger the invocation of a fast retransmit and fast recovery algorithm.


(Fig. 2)

**FIG. 1**

MOBILE IPv6 BASIC OPERATION

**FIG. 2**

COMPARISON OF FLOW CHARTS WITH AND
WITHOUT NEW METHOD IN TIME SCALE

**FIG. 3**

**COMPARISON OF BEHAVIOR OF CONGESTION WINDOW IN RESPONSE
TO HANDOVER WITH AND WITHOUT THE INVENTION**

(19) World Intellectual Property Organization
International Bureau(43) International Publication Date
23 October 2003 (23.10.2003)

PCT

(10) International Publication Number
WO 03/088622 A1(51) International Patent Classification⁷: H04L 29/08, 1/18

(21) International Application Number: PCT/IB03/01342

(22) International Filing Date: 11 April 2003 (11.04.2003)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
PCT/IB02/01181 12 April 2002 (12.04.2002) IB

(71) Applicant (for all designated States except US): NOKIA CORPORATION [FI/FI]; Keilalahdentie 4, FIN-02150 Espoo (FI).

(72) Inventors; and

(75) Inventors/Applicants (for US only): ZHANG, Dongmei [CN/CN]; Building 10, Room 433, Longzhang Road,

Haidian District, Beijing (CN). ZHANG, Runtong [CN/FI]; c/o NOKIA CORPORATION, Keilalahdentie 4, FIN-02150 Espoo (FI). KAN, Zhigang [CN/FI]; c/o NOKIA CORPORATION, Keilalahdentie 4, FIN-02150 Espoo (FI). MA, Jian [FI/FI]; c/o NOKIA CORPORATION, Keilalahdentie 4, FIN-02150 Espoo (FI).


(74) Agent: LESON, Thomas, Johannes, Al; TBK-Patent, Bavariaring 4-6, 80336 München (DE).

(81) Designated States (national): AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NI, NO, NZ, OM, PH, PL, PT, RO, RU, SC, SD, SE, SG, SK, SL, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VC, VN, YU, ZA, ZM, ZW.

(84) Designated States (regional): ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZM, ZW),

[Continued on next page]

(54) Title: SYSTEM, DEVICE AND METHOD FOR IMPROVING THROUGHPUT IN A COMMUNICATION NETWORK, PREFERABLY A MOBILE IPV6-BASED NETWORK



(57) Abstract: The invention relates to a method and system for managing a communication between a first mobile network element and a second network element, wherein the communication is performed via a network on a packet-switched basis with acknowledgment messages acknowledging receipt of packets being returned to the packet sending network element. A congestion control is provided for controlling the number of packets being allowed to be sent before receipt of acknowledgment messages for these packets. The congestion control is adapted to change, when the first network element performs a hand-over and sends a message informing on the I hand-over, so as to provide faster recovery rate after handover as compared to the normal recovery rate after packet loss. At least one of the first and second network element is adapted, when receiving the message, to trigger the invocation of a fast retransmit and fast recovery algorithm. As an alternative, in order to provide the faster recovery rate after handover, a congestion window size may be step-wise increased after handover, or a threshold value defining a change from exponential to linear increase of the congestion window size, may be set to a value which is more than one half of the window size value before handover.



WO 03/088622 A1



Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM),
European patent (AT, BE, BG, CH, CY, CZ, DE, DK, EE,
ES, FI, FR, GB, GR, HU, IE, IT, LU, MC, NL, PT, RO,
SE, SI, SK, TR), OAPI patent (BF, BJ, CF, CG, CI, CM,
GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).

Published:

— with international search report

— before the expiration of the time limit for amending the
claims and to be republished in the event of receipt of
amendments

*For two-letter codes and other abbreviations, refer to the "Guid-
ance Notes on Codes and Abbreviations" appearing at the begin-
ning of each regular issue of the PCT Gazette.*

TITLE**SYSTEM, DEVICE AND METHOD FOR IMPROVING THROUGHPUT
IN A COMMUNICATION NETWORK, PREFERABLY A
MOBILE IPv6-BASED NETWORK****DESCRIPTION****FIELD AND BACKGROUND OF THE INVENTION**

The invention relates to a method and system for improving throughput in a communication network, preferably a Mobile IPv6-based network. IPv6 stands for the Internet Protocol version 6 (as compared to the existing IPv4) and is a standardized protocol. Mobile IPv6 is a standardized protocol which supports mobility in IPv6.

In particular, the present invention is related to a method and system to improve TCP (Transmission Control Protocol) performance, especially the throughput of TCP connection and utilization of the network resource, when a mobile node in the Mobile IPv6 network hands over between two subnets.

TCP (Transmission Control Protocol) is a reliable transport protocol that has been tuned for networks composed of wired links and stationary hosts. It interprets an unexpected increase in delay as packet losses caused by congestion. The congestion control policies have been proved beneficial in improving the overall performance of the networks like the current Internet.

Mobile IPv6 networks, however, will include wireless links and mobile hosts. In Mobile IPv6, a mobile node (MN) is

always addressable by its home address, whether it is currently attached to its home link or is away from home. While a mobile node is attached to some foreign link away from home, it is also addressable by one or more care-of addresses, in addition to its home address. Correspondent node (CN) is any node communicating with the mobile node. After the mobile node acquires its care-of address in a foreign link, it will register the association between the mobile node's home address and this care-of address with home agent and correspondent node by sending a packet containing a "Binding Update" destination option, as shown in Fig. 1.

When TCP is used as the transport protocol, some types of delay and packet loss that are unrelated to congestion will be encountered during mobile node handing over between two subnets.

The problem with existing TCP is that the packets lost during handoff are interpreted as network congestion. In more detail, the typical congestion control mechanisms will misinterpret unexpected increase in delay as packet losses caused by congestion, and may degrade the network performance because the congestion state is followed automatically by the TCP slow start procedure.

25

In Mobile IPv6, there are several types of delay and loss that are unrelated to congestion. First, communications may slow down while the handovers between two subnets occur, packets cannot again be routed to and from the mobile node until the handover completes. During the handover process, there is a time period when the MN is unable to send or receive IPv6 packets both due to link switching delay and IP protocol operations. This time period is referred to as handover latency. In many instances, the handover latency resulting from standard Mobile IPv6 handover procedures could

be greater than what is acceptable to support real-time or delay sensitive traffic.

Second, packets may be lost due to the relatively frequent
5 transmission errors suffered by wireless link. Third, packets may be lost due to the limited buffer in home agent buffering packets when a mobile node is attached to some foreign link away from home.

10 When these unexpected delays are due to handover happen, the typical TCP congestion control will interpret them as network congestion. Therefore, the congestion window shrinks to its minimum value (one segment) abruptly and begins to invoke the slow-start algorithm till an acknowledgment (ACK) reaches TCP
15 transmitter. As ACK reach the TCP transmitter, slow-start algorithm begins to grow the congestion window exponentially until it reaches a threshold ssthresh, then grows it linearly. The threshold ssthresh is set to one half of the congestion window size at the time of the retransmission
20 timeout. After handover completes for long time, the congestion window returns gradually to its previous level before the window shrinks, as shown in Fig 3 by broken lines. Thus it takes a long time after handover completion until the congestion window returns gradually to its previous level.

25 Actually, the slow start algorithm is effective when network congestions are indeed detected. However in the handover scenario, slow start usually is not triggered by network congestions, but by handovers. Hence, the slow recovery of
30 the congestion window due to slow start algorithm after each handover causes to the losses of throughput.

In Mobile IPv6, a handover of a mobile node between two subnets will degrade TCP performance, especially throughput
35 and utilization of network resource.

Although a number of methods such as Fast Handover, G. Dommetry (Editor), A. Yegin, C. Perkins, G. Tsirtsis, K. El-Malki, M. Khalil: "Fast Handovers for Mobile IPv6", Internet
5 Draft, Internet Engineering Task Force (IETF), September 2002, and LMM, Carl Williams, Editor: "Localized Mobility Management Requirements", Internet Draft, Internet Engineering Task Force, December 2002, have been proposed to improve the handover performance in Mobile IPv6, it is a MUST
10 that the packet loss, reordered packets and delayed packets are produced due to handover process not to congestion. According to the TCP principle, TCP assume that packet losses are indications of congestion, but sometimes losses are from corruption on a wireless link, and TCP assumes that
15 significantly reordered packets are indications of congestions, but this is not always the case. Hence, the typical congestion control mechanisms may degrade the network performance. To sum up, in Mobile IPv6, a MN hands over between two subnets will degrade TCP performance, especially
20 throughput and the utilization of network resource.

Because of the key roles of TCP in the Internet, through these years, various attempts have been made to enhance TCP functions. Recently, along with the rapidly development of
25 satellite or mobile technologies, improving TCP's performance on wireless links has been becoming a challenge and an active research topic.

In wired link scenarios, there are many TCP enhancement
30 methods, which are well applied. Among all the amendments to TCP, slow start, congestion avoidance, fast retransmission and fast recovery have been proven very efficient and mature, and well applied. Another example is the Explicit Congestion Notification (ECN). Fast-TCP has recently proposed, and its
35 control philosophy is different from all previous methods.

However, some problems still exist when these methods are used in wireless environment.

Regarding the TCP enhancements on the wireless platform,

5 considerable efforts are devoted to determining the cause of packet drops and accordingly taking control actions.

Generally, forward error correction (FEC), automatic repeat request (ARQ), indirect TCP (I-TCP), snoop, explicit loss notification (ELC), selective ACK (SACK), forward ACK (FACK),
10 new ECN, and Full Rate (FR+) are some possible solutions in this category.

SUMMARY OF THE INVENTION

15

The invention aims, among others, to improve performance, e.g. to provide TCP enhancements for solving handover-related problems.

20 The present invention provides a method, system and/or device as defined in the independent claims or any one of the dependent claims.

The invention preferably relates to IPv6 mobility and TCP
25 optimization methods "fast retransmit" and "fast recovery". In fast retransmit method lost packets are detected in TCP transmitter by means of three or more duplicate ACKs.

The invention further preferably relates to IPv6 handoff (or
30 handover) between two subnets.

The invention provides a method and system for improving throughput in a communication network, preferably a Mobile IPv6-based network.

35

In accordance with one of the aspects of the invention, the invention relates to a case where e.g. CN is taken as the TCP transmitter and MN as the TCP receiver, or vice versa.

5 According to one of the aspects of the invention, when a mobile node after the handoff and e.g. address autoconfiguration in the new subnet sends a binding update message towards the correspondent node, the binding update is interpreted as a signal to a congestion control means, e.g. a
10 TCP layer. The signal indicates to the congestion control means that fast recovery procedures should be initiated, instead of slow start. The signal can be implemented as duplicating ACK packets by the IP layer to the TCP layer. As an alternative, in order to provide the faster recovery rate
15 after handover, a congestion window size may be step-wise increased after handover, or a threshold value defining a change from exponential to linear increase of the congestion window size, may be set to a value which is more than one half of the window size value before handover.

20

One of the objective of the present invention is to provide a method for triggering the fast retransmit and fast recovery mechanism as fast as possible, by means of which the throughput of TCP connection and the utilization of the
25 network resource can be improved.

The objective is achieved by a method, which, according to one of the embodiments, comprises the following steps:

- 1) When a mobile node moves from one subnet into another
30 foreign subnet, it acquires its care-of address in foreign link, e.g. according to the methods of IPv6 Neighbor Discovery;
- 2) the mobile node registers the association between the mobile node's home address and this care-of address with home
35 agent and correspondent node by sending a packet containing a

"Binding Update" destination option;

3) when the correspondent node receives the packet containing the "Binding Update", the Mobile IPv6 software in the correspondent node signals the TCP software;

5 4) the TCP software on correspondent node invokes the fast retransmit and fast recovery mechanism or threshold value setting when it receives the signal from the Mobile IPv6 software.

10 An advantage of the invention is to invoke fast retransmit and fast recovery mechanism other than slow start mechanism after handover completing, or to increase a congestion window size step-wisely after handover, or to increase a threshold value defining a change from exponential to linear increase
15 of the congestion window size, so as to improve TCP performance, especially throughput. Fast retransmit and fast recovery algorithms are known TCP congestion control methods. The idea is that if three or more duplicate ACKs are received by a TCP transmitter, the missing segment will be
20 retransmitted immediately, without waiting for the retransmission timer to expire. Then instead of performing slow-start algorithm, congestion avoidance algorithm is invoked. Invoking fast retransmit and fast recovery algorithms other than slow start will improve throughput of
25 TCP connection.

Another advantage of the invention is that there is one trigger mechanism to invoke fast retransmit and fast recovery algorithms. In Mobile IPv6, fast retransmit and fast recovery
30 algorithms could not be triggered automatically immediately after completion of handovers because ACKs could not be sent until the handover completed. The invention thus provides a trigger to fast retransmit and fast recovery algorithms.

35 A further advantage of the invention is the ability to

trigger fast retransmit and fast recovery algorithms as soon as possible. In Mobile IPv6, after the mobile node acquires its care-of address in foreign link, it will register this care-of address with home agent and correspondent node by sending the "Binding Update" destination option. The "Binding Update" destination option is the earliest signal for the correspondent node to be informed that the handover is successful and will be completed soon. Hence, it is the earliest time for correspondent node to trigger fast retransmit and fast recovery algorithms.

There are key features, either to be provided isolated or in any arbitrary combination, of the present invention which improve earlier solutions: Invocation of fast retransmit and fast recovery mechanism other than slow start mechanism after handover completion; one trigger mechanism to invoke fast retransmit and fast recovery algorithms; triggering fast retransmit and fast recovery algorithms as fast as possible.

Some of the provided advantages are: Improvement of the TCP performance, e.g of TCP throughput; Improvement of the utilization of network resource; Only minor modifications to the TCP and Mobile IPv6 software in TCP transmitter are be made.

BRIEF DESCRIPTION OF THE DRAWINGS

Fig 1 illustrates an embodiment of the invention and illustrates the basic operation in Mobile Ipv6 handover and the process between Mobile Node (MN) and Correspondent Node (CN), for initializing a "Binding Update" destination option;

Fig 2 shows a time scale for comparing flow charts of a first embodiment of a method and device in accordance with

the invention, and of a method not using the first embodiment of the invention;

Fig 3 shows a comparison of the behavior of a congestion
5 window in response to handover with and without the first embodiment of the method and device in accordance with the invention;

Fig 4 illustrates another embodiment of the invention,
10 showing the basic operation in Mobile Ipv6 handover with more details and the process between Mobile Node (MN) and Correspondent Node (CN), for initializing a "Binding Update" destination option;

Fig 5 shows a time scale for comparing flow charts of a
15 second embodiment of a method and device in accordance with the invention, and of a method not using the second embodiment of the invention;

Fig 6 shows a comparison of the behavior of a congestion
20 window in response to handover with and without the second embodiment of the method and device in accordance with the invention;

Fig 7 shows a time scale for comparing flow charts of a
25 third embodiment of a method and device in accordance with the invention, and of a method not using the third embodiment of the invention; and

Fig 8 shows a comparison of the behavior of a congestion
30 window in response to handover with and without the third embodiment of the method and device in accordance with the invention.

35

**DETAILED DESCRIPTION OF PREFERRED EMBODIMENTS OF THE
INVENTION**

- 5 The invention can be implemented e.g. in a TCP sender with small modifications. TCP sender can be any mobile equipments, such as mobile phones, Personal Digital Assistants (PDAs), laptops, which have e.g. mobile IPv6 stack.
- 10 In the below described embodiments of the invention, a message, e.g. Binding Update, is used as a trigger to change the normal congestion control such as TCP congestion control. The subsequent congestion control changing processes after occurrence of the trigger can be different in the embodiments
- 15 in accordance with the present invention. In a first embodiment, a conventional Fast Retransmit and Fast Recovery procedure is invoked after the trigger. Thus, a new trigger is provided for invoking this procedure at an earlier time.
- 20 In another embodiment, a Slow-Start Threshold (SSTHRESH) is increased after occurrence of the trigger. The new SSTHRESH can be any value between old SSTHRESH and old Congestion Window size (CWND). The actual value of the new SSTHRESH may depend on the network performance. In a network with good
- 25 performance, a higher SSTHRESH can be set, and in a network with poor performance, a lower SSTHRESH may be set.

In a further embodiment, the Congestion Window size (CWND) can be increased after occurrence of the trigger. The value

30 of new CWND can be any value from more than the minimum value (one segment) to old CWND. The new CWND may also depend on the network performance. Different values will result in different CWND behavior.

- 35 In other embodiments, the above measures can also be

combined, that is the Slow-Start Threshold (SSTHRESH) and the Congestion Window size (CWND) can both be increased after occurrence of the trigger.

5 In all the embodiments, there are two different scenarios, i.e. MN acting as receiver and MN acting as transmitter (sender). In Figs. 2, 5 and 7, only the flow chart of the first scenario, that is MN acting as receiver and CN acting as transmitter, is presented. The flow charts for the second
10 scenario (CN acting as receiver and MN acting as transmitter) are almost the same and are therefore not shown. The invention covers both scenarios.

Fig 1 illustrates a first embodiment of a communication
15 system in accordance with the present invention and shows a MIP (Mobile IP, IP = Internet Protocol), e.g. mobile IPv6, basic operation during handover (Mobile IPv6 is the protocol that supports mobility in IPv6). A Mobile Node (MN) 1 is represented two times, once attached to its home link (upper
20 position of Fig. 1), and once after moving to another location (lower position of Fig. 1) where the MN 1 is away from home and attached not to its home link but served by another serving entity, i.e. by a foreign link. A Home Agent (HA) 2 is associated to the MN for traffic control. With a
25 Mobile IPv6 Binding Update (BU) message, a remote node such as the MN 1 after moving, may inform any other node such as the HA 2 or CN (Correspondent Node) 7 that all traffic sent to the remote node's home address should be currently sent to another address, the so called care-of-address.

30

The Mobile Node (MN) 1 detects his movement e.g. by receiving a Routing advertisement from a router, and generates his Care-of-Address (COA) with a stateless or a stateful address allocating procedure. MN 1 sends this information to his Home
35 Agent (HA) 2 by a Binding Update (BU) message 5. HA 2

modifies the information on the address entry in its Binding Cache and e.g. returns a Binding Acknowledgement (BAck) message to MN 1. A same Binding Update message 3 is also sent from MN 1 to CN 7. This BU message 3 allows route
5 optimization: The CN 7 sends the data directly to the MN 1 and vice versa.

Packets from a Correspondent Node (CN) 7 or any other node to the shadow of the Home Address of MN 1 are blocked by the HA
10 2 and are tunneled to the MN 1 for the destination in the Binding Cache. The connection and traffic between MN 1, HA 2, and CN 7, is effected via the internet 6. Link 4 represents any connection between MN 1 and any other node handled via internet 6.

15 Fig. 2 shows flow charts with a time scale for comparing the previous method and a first embodiment of the method/system according to the invention. The time axis is shown at the right-hand side of Fig. 2. The left column S_A represents the
20 IP layer in the MN 1. The middle column S_B shows the normal previous behaviour of CN 7 when not employing the embodiment according to the invention.

The right-hand column S_C shows the behaviour of CN 7 when
25 employing a first embodiment (embodiment 1) of the method and system according to the invention.

In Fig. 2, as well as in Figs. 3, and 5 to 8, the indicated time points t_1 to t_5 represent the following: t_1 : Handover
30 begin; t_2 : Binding Update trigger; t_3 : Arrival of first ACK; t_4 : Congestion window size back to the value before handover in the embodiments of the present invention; t_5 : Congestion window size back to the value before handover in prior art.

35 In step S1 of Fig. 2, it is assumed that the MN 1 moves into

a foreign subnet, that is a handover is performed. In step S2, the MN 1 acquires a new care-of address (CoA), and sends, in step S3, a message, preferably a binding update message, to HA 2 and/or CN 7.

5

In step S4 of the middle column S_B showing the normal previous behaviour of CN 7, and of the right column S_C showing the behaviour of CN 7 according to the first embodiment, the congestion window shrinks to the minimum value as a result of the handover. The size of the congestion window cwnd is set to 1 (cwnd=1).

In step S5 of the middle column S_B showing the normal previous behaviour of CN 7, CN 7 receives the Binding Update message either directly from MN 1, or from HA 2, but does nothing to TCP.

In step S6, it is assumed that the CN 7 sends data and waits for receipt of an Acknowledgment message ACK confirming that MN 1 has received the sent data.

If no ACK is received in step 7, the routine proceeds to step S8 in which TCP Timeout is checked as usual. Due to the handover, some packets will get lost so that the ACKs are not properly returned. As long as TCP has not timed out, the waiting loop is executed via steps S8, S7, for the set waiting period. After TCP timeout, the answer of checking step S8 is "Yes" and the program proceeds to step S9, in which the data are resent. Thereafter, the routine jumps back to step S7. This loop may be repeated for a defined number.

If an ACK is received in step 7, the routine proceeds to step S10 wherein the congestion window is controlled to increase, returning gradually to the previous value before handover. Thus, the customary slow start mechanism is effected. . In

step S11, the congestion window has finally returned to the previous value before handover.

Now, the right-hand column S_c is discussed which shows the
5 behaviour of CN 7 when employing the first embodiment of the
method and system according to the invention. In step S12,
the CN 7 receives the Binding Update message, and then
informs its TCP software/structure thereon (step S13). The
TCP software responds by executing step S14, i.e. it triggers
10 its fast retransmit & fast recovery mechanism which may be
the customary fast retransmit & fast recovery mechanism.
Thus, the CN 7 does not wait for TCP timeout but immediately
starts the fast retransmit/recovery mechanism for bringing
back the congestion window to its value before the handover
15 as quickly as possible.

As an example, according to one of the preferred embodiments,
the value ssthresh may be increased or set to the previous
value of the old congestion window in step S12.

20

In step S15, the congestion window has thus returned to the
value before handover very fast.

Fig 3 shows a comparison of the behavior of the congestion
25 window in response to handover with and without employing the
above discussed first embodiment of the system and method
according to the invention. The X axis of Fig. 3 represents
time, and the Y axis represents the congestion window size
and thus TCP throughput.

30

The solid line illustrates the behavior of the congestion
window in response to handover when employing the first
embodiment of the invention, i.e. when triggering the fast
retransmit & fast recovery directly after handover detection,
35 that is receipt of the message confirming handover completion

such as the BU (Binding Update) message.

The dotted line of Fig. 3 shows the conventional behavior of the congestion window in response to handover when not using
5 the invention, i.e when employing the slow start process.

As shown in Fig. 3, the first embodiment of the invention provides a very fast growth of the congestion window size and thus system performance and throughput, in a step-wise and
10 subsequent ramp-like fashion, after any handover occurrence.

Contrary thereto, as shown by the dotted line in Fig. 3, the growth of the congestion window size as well as momentary window size, and thus system performance and throughput, is
15 much slower with the conventional slow start technique after handover.

In this and the below described embodiments, when the binding updates to the correspondent node should be handled by an
20 agent acting on behalf of the correspondent node, the agent is preferably programmed to send either the binding update messages, or a command for starting the fast retransmit & fast recovery, to the correspondent node, i.e. to the TCP transmitter.

25

According to another embodiment, the CN is adapted to check, when it receives a Binding Update message, whether it has sent any not yet acknowledged data, i.e. it is waiting for acknowledgment messages, or whether it has any data to be
30 sent actually. When the CN does not have any unacknowledged data, i.e. it is not waiting for acknowledgment messages, or does presently not intend to send any data, the correspondent node may be programmed simply not to do anything special if it gets a Binding Update message. When the check should
35 however reveal that the CN has sent any not yet acknowledged

data, i.e. it is waiting for acknowledgment messages, or intends to send any data, the above mentioned fast retransmit & fast recovery method of the correspondent node is triggered.

5

The functioning of the method and system according to the invention can be tested by pretending to lose one or more packets, and checking the actions taken by the correspondent node when it gets a Binding Update message.

10

Buffer management (BM) might cause duplication of packets which can be dealt with in the MN, but wastes radio resources. An option is to agree between the MN and the CN upon the use of the disclosed method. This approach can

15

bypass problems with BM and hierarchic mobility management.

The present invention thus provides a method and system for improving TCP performance, especially throughput and utilization of network resource.

20

In the following, some basic explanations on the algorithms mentioned above are given with reference to RFC 2001.

Slow Start Algorithm:

25

The slow start algorithm adds another window to the sender's TCP: the congestion window "cwnd", so as to allow the rate of injecting new packets into the network to be the rate of returning acknowledgments by the other end.

30

When a new connection is established with a host on another network, the congestion window is initialized to one segment. Each time an ACK is received, the congestion window is increased by one segment. The sender can transmit packets up to the minimum of the congestion window and the advertised

35

window. The congestion window provides flow control imposed

by the sender, while the advertised window is a flow control imposed by the receiver. The sender flow control is based on the sender's assessment of perceived network congestion.

- 5 The sender starts by transmitting one segment and waiting for its ACK. When that ACK is received, the congestion window is incremented to two so that two segments can be sent. When each of those two segments is acknowledged, the congestion window is increased to four, providing approximately
10 exponential growth. When the capacity of the network is reached, packets may be lost. This informs the sender that its congestion window has grown too large.

Congestion Avoidance:

- 15 Congestion avoidance deals with lost packets. Congestion can e.g. occur when high data rate input streams arrive at a router with insufficient output capacity. A loss of a packet signals congestion somewhere in the network between the source and destination. There are two possible indications of
20 packet loss: occurrence of timeout, or receipt of duplicate ACKs. When congestion occurs TCP slows down its transmission rate of packets into the network, and invokes the slow start algorithm.

- 25 Congestion avoidance and slow start require that two variables be maintained for each connection: a congestion window, *cwnd*, and a slow start threshold size. Slow start continues until TCP is halfway to where it was when congestion occurred, and then congestion avoidance takes
30 over. Congestion avoidance dictates that *cwnd* be incremented each time an ACK is received, with linear growth of *cwnd*.

Fast Retransmit:

- The Fast Retransmit algorithm is a modification to the
35 congestion avoidance algorithm. Note that TCP may generate an

immediate acknowledgment (a duplicate ACK) when an out-of-order segment is received. This duplicate ACK should not be delayed. This duplicate ACK informs the other node that a segment was received out of order.

5

Since TCP does not know whether a duplicate ACK is caused by a lost segment or just a reordering of segments, it waits for a small number of duplicate ACKs to be received. If there is just a reordering of the segments, there will be only one or
10 two duplicate ACKs before the reordered segment is processed, which will then generate a new ACK. If three or more duplicate ACKs are received in a row, this will normally be caused by having lost a segment during transmission. TCP then performs a retransmission of the missing unacknowledged
15 segment, without waiting for a retransmission timer to expire.

Fast Recovery

After fast retransmit has resent the missing segment,
20 congestion avoidance (not slow start) is performed. This is the fast recovery algorithm. It is an improvement that allows high throughput under moderate congestion, especially for large windows.

25 The fast retransmit and fast recovery algorithms are usually implemented together as follows.

1. When the third duplicate ACK is received in succession, the slow start threshold size sst is set e.g. to one-half of the current congestion window, cwnd, and the missing segment
30 is retransmitted. Then, cwnd is set to sst plus 3 times the segment size. This increases the congestion window by the number of segments received by the other end.

2. Each time another duplicate ACK arrives, cwnd is incremented by the segment size, so as to increase the
35 congestion window each time an additional segment has left

the network.

3. When a next ACK arrives that acknowledges new data, this ACK will normally be the acknowledgment of the retransmission performed in step 1. This ACK acknowledges all the
5 intermediate segments sent between the lost packet and the receipt of the first duplicate ACK. The cwnd is then set to sst, e.g. to the value of sst set in step 1. This step provides congestion avoidance, since TCP is reduced to one-half of the rate before losing the packet.

10

Preferred embodiments of the invention relate to TCP performance enhancement during handovers in MIP such as Mobile IPv6 network. The embodiments propose a mechanism to undo an unnecessary congestion control triggered by
15 reordered, delayed or lost packets due to handover.

The basic idea of some embodiments of the invention is to use a signal indicating handover completion, e.g. a binding update message, and then, recover the threshold ssthresh to a
20 higher value than conventionally, e.g. to more than one-half of, up to the value of the previous congestion window, instead of only one half of this value. By this new higher ssthresh, the congestion window can be restored faster. Therefore, the TCP throughput and utilization of network
25 resource are improved.

These or other embodiments of the invention basically belong to MIP focus area. A basic idea of these and some other but not necessarily all embodiments of the invention is:

- 30 1. Using a message, e.g. Binding Update, as an indication of successfully completed handover, and/or
2. After this message, e.g. Binding Update, triggering a mechanism to change the slow-start parameter in order to restore the congestion window faster than regular TCP.

35

The above embodiments may be considered as a conservative scheme, which changes the threshold in slow-start algorithm (sssthresh). It increases sssthresh to the value of the previous congestion window. Because the congestion window grows exponentially before sssthresh and grows linearly after sssthresh, higher sssthresh lets the congestion window grows faster.

This alternative 2. is a moderate scheme which changes the initial size of congestion window. It directly increases the congestion window to a high proper value. This value can be a predetermined value based on network performance or a dynamic value based on real-time network measurement. Better result on TCP throughput can be obtained.

The invention may be used in e.g. proxies and servers without standardization, in TCP terminals, such as mobile phone, PDA, laptop, or the like.

In one or more of the embodiments of the invention, a fast retransmit and fast recovery mechanism is initiated instead of keeping slow-start initiate after handover completion message, e.g. Binding Update.

The below described embodiment of the invention pays attention to the two scenarios that MN is taken as the TCP receiver and sender.

IPv6 [Internet Protocol version 6], especially Mobile IPv6, is a research field, in which an Internet draft on mobile IPv6 is likely to become a RFC in the near future. However, if the MN is at some geographical and topological distance away from the HA and CN, the amount of time involved in sending the binding updates may be greater than hundred milliseconds. This latency in routing update may cause poor

TCP performance. The described embodiments provide TCP enhancement during handovers in mobile IPv6. According to some embodiments, a mechanism is provided which recovers the slow-start threshold `ssthresh` to more than half of, up to the previous value of the old congestion window after a handover completion if the timeout is caused by the handover. This improves TCP throughput. For a flow with a large congestion window `W`, a halving of the congestion window can be a significant performance reduction as it takes at least $W/2$ round-trip times for the flow to recover its old congestion window.

There are two scenarios described in the following, with MN acting as a receiver and MN as a sender.

15

MN acting as a receiver: If the CN determines that the packet loss, reordered packets and delayed packets are produced due to handover process and not to congestion, then the CN may implement the option of undoing the halving in the congestion window, by means of which the throughput of TCP connection and the utilization of network resource can thus be improved. When the CN receives the Binding Update from MN, this mechanism is triggered.

25 The objective is achieved by an algorithm, which comprises the following steps:

- (1) When a MN moves from one subnet into another foreign subnet, it acquires its care-of-address in the foreign link, by using the IPv6 Neighbour Discovery or other methods;
- (2) the MN registers the association between the MN's home address and the current care-of-address with its home agent and the CN by sending a packet containing a "Binding Update" destination option;
- 35 (3) whenever the CN receives a "Binding Update", the

software, e.g. Mobile IPv6 software, in the CN signals the TCP software;

(4) the TCP software on CN stepwisely increases the slow-start threshold ssthresh to a value of more than half of, up to the previous value of the old congestion window if slow-start happened, effectively slow starting until the congestion window has reached its old value. In addition to avoid the unnecessary retransmits, CN may preferably adjust the duplicate acknowledgement threshold or the retransmit timeout parameters so as to reduce retransmits.

MN acting as a sender: If the MN determines that packet loss, reordered packets and delayed packets are produced due to handover process but not to congestion, then the MN preferably has the option, means and functions of undoing the halving in the congestion window, that is of increasing the slow-start threshold ssthresh to a value of more than half of, up to the previous value of the old congestion window. Thereby, the throughput of TCP connection and the utilization of network resource can thus be improved. When the MN forms the Binding Update, this mechanism is triggered in the MN.

The objective is achieved by an algorithm, which comprises the following steps:

25

(1) When a MN moves from one subnet into another foreign subnet, it acquires its care-of-address in the foreign link, e.g. by using the IPv6 Neighbor Discovery;

(2) whenever the MN forms a "Binding Update", the software, e.g. Mobile IPv6 software in the MN signals the TCP software;

(3) the TCP software on MN increases the slow-start threshold ssthresh to the previous value of the old congestion window if slow-start happens, effectively slow starting until the congestion window has reached its old value. In addition to avoid the unnecessary retransmits, MN may be equipped to

adjust the duplicate acknowledgement threshold or the retransmit timeout parameters.

5 The (previous) slow-start threshold ssthresh value of the old congestion window may be stored in the MN and/or in the CN, e.g. if slow-start happens,

10 These embodiments of the invention present a mechanism to undo unnecessary congestion control responses to reordered or delayed or lost packets due to handover. In Mobile IPv6, after a MN acquires its care-of-address in a foreign link, it will register this care-of-address with its home agent and the CN by sending the "Binding Update" destination option. The "Binding Update" destination option is the earliest
15 signal for the CN to be informed that the handover is successful and will complete soon. Hence, it is the earliest time for CN and MN to be able to undo congestion control.

20 If congestion control in TCP does not run during handover which performance is good enough, the proposed mechanism is preferably not in effect.

There are key actions in the present invention to improve earlier solutions:

- 25
- Undo unnecessary congestion control due to handover after a handover completes,
 - Recover previous control parameters as fast as possible.

Some advantages of the embodiments are:

- 30
- Improving the TCP throughput
 - Improving the utilization of network resource
 - Only minor modifications to the TCP and Mobile IPv6 software in TCP transmitter needed

35 The invention can be implemented in TCP terminals with small

modifications. TCP terminals could be any mobile equipment, such as mobile phones, PDAs and laptops, which have mobile IPv6 stack. The TCP performance can be improved when this method is used.

5

Fig. 4 shows another embodiment of the invention employing the above described means and functions of Mobile IP, preferably Mobile IPv6, basic operation. Reference numerals identical to the reference numerals used in Fig. 1 designate identical or at least similar means and structures, as described above. The network environment and handover process are as same as the embodiment shown in Figure 1. Figure 4 provides more details and shows some network elements which are not shown in Figure 1. The MN 1 has a home network 10 providing home link, home address, and home subnet prefix, and comprising an home agent 2. When the MN 1 has moved to another network, data/messages/information are exchanged between MN 1 and home agent 2 or CN 7 via internet 6 and foreign/visited or access networks 11, 13 having access routers 12, 14, as shown in Fig. 4. Network 11 provides foreign link, care-of address, and foreign subnet prefix. A Binding Update message is generated in and sent from the MN 1 via internet 6 to the home network 10.

25 Figs. 5 and 6 illustrate a second embodiment of the method/system according to the invention, and show flow charts with a time scale for comparing the prior method and the second embodiment. The time axis is shown at the right-hand side of Fig. 5. As mentioned above, the time points t1 to t5 represent the following: t1: Handover begin; t2: Binding Update trigger; t3: Arrival of first ACK; t4: Congestion window size back to the value before handover in the embodiments of the present invention; t5: Congestion window size back to the value before handover in prior art.

35

The left column S_A of Fig. 5 represents the IP layer in the MN 1. The middle column S_B shows the normal previous behaviour of CN 7 when not employing the embodiment according to the invention. The left column S_A and middle column S_B of Fig. 5 are identical to the left and middle columns of Fig. 2 so that it is referred to the above description of the steps and functions of these columns, as well as of step S4 of the right-hand column S_C .

10 The right-hand column S_C of Fig. 5 shows the functioning of CN 7 when employing the second embodiment (embodiment 2) of the method and system according to the invention. In step S12, the CN 7 receives the Binding Update message, and then informs its TCP software/structure thereon (step S13). The TCP software responds by executing step S16, i.e. it immediately increases the threshold value `ssthresh` to a value "New `ssthresh`" higher than the previous customary value "old `ssthresh`", as shown in Fig. 6.

20 The threshold value `ssthresh` is thus set to be higher than the value set according to the prior method (in which the `ssthresh` value was set to one half of the previous value before handover begin, see Fig. 6 "OLD `ssthresh`"), for example to a range of 1.1 to 2.0 of the value "old `ssthresh`", more preferably 1.5 to 2.0 of the previous value. The system then waits for acknowledgments ACK as usual, similar to steps S5 to S10 of the middle column S_B of Fig. 5.

30 Upon receipt of ACKs (step S17), the congestion window size is exponentially increased up to the value "new `ssthresh`". Thereafter, the congestion window size linearly increases up to the maximum value (value before handover), as shown in Fig. 6. The congestion window size is hence returned to the value before handover much quicker than in the previous method.

Fig 6 shows a comparison of the behavior of the congestion window in response to handover with and without employing the above discussed second embodiment of the system and method according to the invention. The X axis of Fig. 6 represents time, and the Y axis represents the congestion window size and thus TCP throughput. The solid line illustrates the behavior of the congestion window in response to handover when employing the second embodiment of the invention, i.e. when increasing the congestion window size directly after handover detection, that is after receipt of the message confirming handover completion such as the BU (Binding Update) message. The dotted line of Fig. 6 shows the conventional behavior of the congestion window in response to handover when not using the invention, i.e when employing the old threshold value. After handover begin the width cwnd of the congestion window is reduced to the lowest value. After handover end, the width of the congestion window is exponentially increased to the ssthresh value. As shown in Fig. 6, the second embodiment of the invention provides a very fast growth of the congestion window size and thus system performance and throughput, after any handover occurrence.

In accordance with a further embodiment of the invention illustrated in Figs. 7 and 8, the width of the congestion window is stepwise increased at the end of the handover, e.g. when sending or receiving a binding update message or packet.

Similar to the above described embodiments, the objective of this embodiment is to improve the throughput of TCP connection and the utilization of the network resource during the MN hands over. The objective is achieved by immediately increasing the congestion window to a high proper value while

the handover finished, not as usual which relies on the TCP slow-start mechanism to recover from the minimal initial window (usually the initial window is only 1 segment).

5 When the MN acts as the TCP sender, the method comprises the following steps:

1) When MN moves from one subnet into another foreign subnet, it acquires its care-of address in foreign link, according to the methods e.g. of IPv6 such as Neighbour Discovery or other

10 methods;

2) By sending "Binding Update" message, the MN registers the association between the MN's home address and its care-of address with home agent (HA) and CN;

3) After MN sends "Binding Update" message, the Mobile IPv6 software in the MN informs the TCP software in the MN of the handover;

4) The TCP software on MN increases the congestion window size to a proper value instead of 1 segment when it receives the signal from the Mobile IPv6 software.

20

The same function may also take place in the CN when it is informed on successful handover, e.g. by receiving a BU message.

25 Figs. 7 and 8 illustrate this third embodiment of the method/system according to the invention, and show flow charts with a time scale for comparing the previous method and the second embodiment. The time axis is shown at the right-hand side of Fig. 7. As mentioned above, the time points t1 to t5 represent the following: t1: Handover begin;

30 t2: Binding Update trigger; t3: Arrival of first ACK; t4: Congestion window size back to the value before handover in the embodiments of the present invention; t5: Congestion window size back to the value before handover in prior art.

35

The left column S_A of Fig. 7 represents the IP layer in the MN 1. The middle column S_B shows the normal previous behaviour of CN 7 when not employing this embodiment according to the invention. The left column S_A and middle
5 column S_B of Fig. 7 are identical to the left and middle columns of Fig. 2 and 5 so that it is referred to the above description of the steps and functions of these columns, as well as of step S4 of the right-hand column S_C .

10 The right-hand column S_C of Fig. 7 shows the functioning of CN 7 when employing the third embodiment (embodiment 3) of the method and system according to the invention. In step S12, the CN 7 receives the Binding Update message, and then informs its TCP software/structure thereon (step S13). The
15 TCP software responds by executing step S18, i.e. it immediately increases the width or size of the congestion window in a stepwise manner to a proper value. This value can be predetermined based on the network performance and/or can be dynamic updated based on network measurement. It may be
20 equal to one half of the window size value before handover, or may be lower or higher than one-half of this value. A value of at least one-half of the window size value before handover is preferred. The system then waits for
25 acknowledgments ACK as usual, similar to steps S5 to S10 of the middle column S_B of Fig. 5. After receipt of the first ACKs at time t_3 , the congestion window size is linearly increased up to the window size value before handover (time t_4). Thus the window size is very rapidly brought back to the maximum admissible size under the present conditions, as
30 shown in Fig. 8.

Fig 8 shows a comparison of the behavior of the congestion window in response to handover with and without employing the above discussed third embodiment of the system and method
35 according to the invention. The X axis of Fig. 8 represents

time, and the Y axis represents the congestion window size and thus TCP throughput. The solid line illustrates the behavior of the congestion window in response to handover when employing the third embodiment of the invention, i.e.

5 when increasing the congestion window size directly after handover detection, that is after receipt of the message confirming handover completion such as the BU (Binding Update) message. The dotted line of Fig. 8 shows the conventional behavior of the congestion window in response to
10 handover when not using the invention, i.e. when employing the old threshold value and old window size. After handover begin (t1) the width cwnd of the congestion window is reduced to the lowest value. After handover end (t2), the width of the congestion window is stepwise increased to the . As shown in
15 Fig. 8, the third embodiment of the invention provides a very fast growth of the congestion window size and thus system performance and throughput, after any handover occurrence.

An advantage of the invention is to increase the transmitting
20 rate immediately after the handover finish by increasing the initial window of slow-start mechanism, so as to improve the throughput just after the handover finish, and utilization of network resource.

25 Another advantage of the invention is to use a "handover successful" message or "handover completed" message such as the "Binding Update" message as the trigger to begin the transmission as soon as possible, instead of waiting for the recovery of TCP mechanism itself.

30 As mentioned above, in current Mobile IPv6 networks, the duration time of handover of MN between two subnets is quite long, compared e.g. with the Round-trip time (RTT). Even when using enhanced handover mechanisms, such as Fast Handover
35 proposed in IETF, the handover time is still a multiple of

RTT. The long handover time usually will result in the timeout in the TCP sender, and the congestion window (CWND) in the TCP sender will decrease to 1 MSS and invoke the slow-start mechanism in prior art devices. In fixed networks, the timeout is the signal of network congestion. In order to alleviate the network load during congestion, the transmission rate i.e. the congestion window will be decreased dramatically, saying 1 segment. However, in Mobile IPv6 networks, misinterpreting the timeout due to handover as congestion will induce the throughput degrade and also underutilize the network resources.

As shown in the Figures, at time t_1 , MN begins a handover. The handover will need some time until MN sends a "binding update" message at time t_2 . However, in the TCP layer, the TCP sender does not know anything about the handover. During the handover, the timeout may happen several times, and the TCP sender retransmits one packet after each timeout. In the prior art, until time t_3 , the TCP sender could successfully retransmit the packets, with the congestion window size 1. Then in the prior art slow-start process, the congestion window increases one by one with every new ACK arriving. This prior art slow-start process is illustrated by the dotted lines in Fig. 8 (denoted "previous method").

The present invention improves the TCP performance in the current situation. The congestion window size may be stepwise increased at the time of sending or receiving the indication of handover end, that is at time t_2 . The congestion window size may be stepwise, i.e. immediately increased to a proper determined value. The determined value may e.g. lie in the range of from 20 % to 100% of the size of the congestion window immediately before handover begin at time t_1 . A preferred determined value can for instance be one half (50%) of the previous congestion window size before handover begin

at time t_1 . The determined value can for instance also be higher than one half, e.g. 100% of the previous congestion window size before handover begin at time t_1 , t_4 .

- 5 There are key actions in the present embodiments of the invention to improve earlier solutions: Taking advantage of, i.e. using a message, for example a MIP message such as the Mobile IPv6 message to trigger TCP optimisation, the transmission can begin earlier than usual. Further, fast or
10 stepwise increase of the congestion window to a proper value after handover, eliminates the slow-start effect. The congestion window can be recovered to an appropriate value faster than usual.
- 15 Advantages are that the TCP throughput is improved, the utilization of network resource is increased, and only minor modifications to the TCP and Mobile IPv6 software in TCP transmitter are needed, which are easy to implement in network elements such as mobile phones, terminals, nodes etc.
20

From the congestion window curve, with this embodiment of the present invention the congestion window will increase earlier and faster than in the normal situation. With the present
25 invention, the throughput is improved during handover.

The specific features of the above discussed embodiments can also be applied in any arbitrary combination. For instance, the congestion window size may be stepwise increased to a
30 predetermined value (lower than one-half of the window size value before handover) after the handover complete message, e.g. BU message, and thereafter be exponentially increased to another threshold value $ssthresh$ higher than one-half of the window size value before handover, with a final linear
35 increase up to the maximum admissible value.

The congestion control means of the first and second network elements, i.e. the mobile node and the correspondent node, may be implemented using TCP (Transport Control Protocol) software, preferably a Mobile IPv6 software.

Although the invention has been described above with reference to specific embodiments, the scope of the invention also covers any alterations, additions, modifications, and omissions of the disclosed features.

CLAIMS

5

1. Method for managing a communication between a first network element and a second network element, wherein the communication is performed via a network on a packet basis,

10 acknowledgment messages acknowledging receipt of packets are returned to the network element having sent these packets, and

a congestion control is performed which variably defines an allowable number of packets which can be sent before
15 receipt of acknowledgment messages for these packets, wherein said allowable number of packets is reduced in case of packet loss during transmission,
wherein, when the first network element performs a hand-over and sends a message informing the network or a network
20 element on the hand-over, the network or network element changes the congestion control to provide faster recovery rate of said allowable number after handover as compared to the recovery rate of said allowable number after packet loss.

25 2. Method according to claim 1, wherein the congestion control provides a congestion window of variable size, the size of the congestion window defining said allowable number of packets which can be sent before receipt of acknowledgment messages for these packets, and the
30 size being controlled dependant on the number of sent packets for which no acknowledgment messages have been received so that the window size is reduced in case of packet loss during transmission,
wherein, when the first network element performs a hand-over
35 and sends a message informing the network or a network

element on the hand-over, the network or network element changes the congestion window size control to provide faster recovery rate of the window size after handover as compared to the recovery rate of the window size after packet loss.

5

3. Method according to claim 1 or 2, wherein said congestion control is performed in at least one of the first and second network elements.

10

4. Method according to any one of the preceding claims, wherein the first network element is a mobile node which, when moving from one subnet into another foreign subnet, acquires a care-of address, and sends said message to its home network and/or to a correspondent node informing the network or node on the care-of-address.

15

5. Method according to any one of the preceding claims, wherein said message is a "Binding Update" message.

20

6. Method according to any one of the preceding claims, wherein said second network element comprises a fast retransmit and fast recovery algorithm so as to provide said faster recovery rate, wherein, when the message is sent from the first network element to the second network element, the second network element, when receiving the message, triggers the invocation of said fast retransmit and fast recovery algorithm.

25

7. Method according to any one of the preceding claims, wherein said first network element comprises a fast retransmit and fast recovery algorithm so as to provide said faster recovery rate, and is adapted to trigger, when generating said message, the invocation of said fast retransmit and fast recovery algorithm.

35

8. Method according to any one of the preceding claims, wherein the faster recovery rate includes a step of increasing the size of a congestion window in a step-wise manner.

5

9. Method according to claim 8, wherein the size of the congestion window is step-wise increased to 20% to 100% of the size of the congestion value before start of the handover.

10

10. Method according to claim 9, wherein the size of the congestion window is step-wise increased to at least approximately 50% of the size of the congestion value before start of the handover.

15

11. Method according to any one of the preceding claims, wherein the faster recovery rate is implemented by increasing the size of a congestion window in a step-wise manner to a value lying in a range from more than a minimum window size up to, and including the size of the window before handover, and by subsequent ramp-like or exponential increase of the congestion window size.

20

12. Method according to any one of the preceding claims, wherein the congestion control includes increasing the size of a congestion window in an exponential manner up to a threshold value and a subsequent ramp-like increasing of the congestion window size, wherein the faster recovery rate is implemented by setting the threshold value to at least one-half of, and up to, the previous value of the congestion window before start of the handover.

25

30

13. Method according to any one of the preceding claims, wherein the second network element is a correspondent node.

35

14. Method according to any one of the preceding claims, wherein at least one of the first and second network elements comprises a congestion control means, and wherein when generating or receiving said message, the first and/or second
5 network element informs its congestion control means which in response triggers the invocation of a fast retransmit and fast recovery algorithm.

15. Method according to any one of the preceding claims,
10 wherein at least one of the first and second network elements comprises a congestion control means, wherein the network element when generating or receiving said message, sends a signal to the congestion control means, the signal indicating to the congestion control means that the congestion control
15 is to be changed so as to provide said faster recovery rate.

16. Method according to claim 15, wherein the signal is implemented by duplicating ACK packets by an IP layer function to a TCP layer function.
20

17. Method according to any one of the preceding claims, wherein the communication between the first and second network elements is an Mobile IPv6-based communication.

25 18 System for managing a communication between a first network element and a second network element, wherein the communication is performed via a network on a packet basis, and acknowledgment messages acknowledging receipt of packets are returned to the network element having sent these
30 packets, comprising

congestion control means for performing a congestion control which variably defines an allowable number of packets which can be sent before receipt of acknowledgment messages for these packets, wherein said allowable number of packets
35 is reduced in case of packet loss during transmission,

wherein, when the first network element performs a hand-over and sends a message informing the network or a network element on the hand-over, the congestion control means changes the congestion control to provide faster recovery
5 rate of said allowable number after handover as compared to the recovery rate of said allowable number after packet loss.

19. System according to claim 18, wherein
the congestion control means provides a congestion window of
10 variable size, the size of the congestion window defining said allowable number of packets which can be sent before receipt of acknowledgment messages for these packets, and the size being controlled dependant on the number of sent packets for which no acknowledgment messages have been received so
15 that the window size is reduced in case of packet loss during transmission,
wherein, when the first network element performs a hand-over and sends a message informing the network or a network element on the hand-over, the congestion control means is
20 adapted to change the congestion window size control to provide faster recovery rate of the window size after handover as compared to the recovery rate of the window size after packet loss.

25 20. System according to claim 18 or 19, wherein said congestion control means is provided in at least one of the first and second network elements.

21. System according to any one of the preceding system
30 claims, wherein the first network element is a mobile node which, when moving from one subnet into another foreign subnet, acquires a care-of address, and sends said message to its home network informing the latter on the care-of-address.

35 22. System according to any one of the preceding system

claims, wherein said message is a "Binding Update" message.

23. System according to any one of the preceding system
claims, wherein said second network element comprises a fast
5 retransmit and fast recovery algorithm so as to provide said
faster recovery rate, wherein, when the message is sent from
the first network element to the second network element, the
second network element, when receiving the message, triggers
the invocation of said fast retransmit and fast recovery
10 algorithm.

24. System according to any one of the preceding system
claims, wherein said first network element comprises a fast
retransmit and fast recovery algorithm so as to provide said
15 faster recovery rate, and is adapted to trigger, when
generating said message, the invocation of said fast
retransmit and fast recovery algorithm.

25. System according to any one of the preceding system
20 claims, wherein the faster recovery rate includes a step of
increasing the size of a congestion window in a step-wise
manner.

26. System according to claim 25, wherein the size of
25 the congestion window is step-wise increased to 20% to 100%
of the size of the congestion value before start of the
handover.

27. System according to claim 26, wherein the size of
30 the congestion window is step-wise increased to at least
approximately 50% of the size of the congestion value before
start of the handover.

28. System according to any one of the preceding system
35 claims, wherein the faster recovery rate is implemented by

increasing the size of a congestion window in a step-wise manner to a value lying in a range from more than a minimum window size up to, and including the size of the window before handover, and by subsequent ramp-like or exponential
5 increase of the congestion window size.

29. System according to any one of the preceding system claims, wherein the congestion control includes increasing the size of a congestion window in an exponential manner up
10 to a threshold value and a subsequent ramp-like increasing of the congestion window size, wherein the faster recovery rate is implemented by setting the threshold value to at least one-half of, and up to, the previous value of the congestion window before start of the handover.

15

30. System according to any one of the preceding system claims, wherein the second network element is a correspondent node.

20 31. System according to any one of the preceding system claims, wherein at least one of the first and second network elements comprises a congestion control means, and wherein when generating or receiving said message, the first and/or second network element informs its congestion control means
25 which in response triggers the invocation of a fast retransmit and fast recovery algorithm.

32. System according to any one of the preceding system claims, wherein at least one of the first and second network
30 elements comprises a congestion control means, wherein the network element when generating or receiving said message, sends a signal to the congestion control means, the signal indicating to the congestion control means that the
congestion control is to be changed so as to provide said
35 faster recovery rate.

33. System according to claim 32, wherein the signal is implemented by duplicating ACK packets by an IP layer function to a TCP layer function.

5

34. System according to any one of the preceding system claims, wherein the communication between the first and second network elements is an Mobile IPv6-based communication.

10

35. Network element to be used in a system for managing a communication between network elements, preferably as defined in claim 18, wherein the communication is performed via a network on a packet basis, and acknowledgment messages
15 acknowledging receipt of packets are returned to the network element having sent these packets, comprising

congestion control means for performing a congestion control which variably defines an allowable number of packets which can be sent before receipt of acknowledgment messages
20 for these packets, wherein said allowable number of packets is reduced in case of packet loss during transmission, wherein, when the network element performs a hand-over and sends a message informing the network or a network element on the hand-over, the congestion control means changes the
25 congestion control to provide faster recovery rate of said allowable number after handover as compared to the recovery rate of said allowable number after packet loss.

36. Network element according to claim 35, wherein
30 the congestion control means provides a congestion window of variable size, the size of the congestion window defining said allowable number of packets which can be sent before receipt of acknowledgment messages for these packets, and the size being controlled dependant on the number of sent packets
35 for which no acknowledgment messages have been received so

that the window size is reduced in case of packet loss during transmission,

wherein, when the network element performs a hand-over and sends a message informing the network or a network element on

5 the hand-over, the congestion control means changes the congestion window size control to provide faster recovery rate of the window size after handover as compared to the recovery rate of the window size after packet loss.

10 37. Network element according to claim 35 or 36, wherein said network element comprises a fast retransmit and fast recovery algorithm so as to provide said faster recovery rate, and is adapted to trigger, when generating said message, the invocation of said fast retransmit and fast
15 recovery algorithm.

38. Network element according to claim 35, wherein the faster recovery rate includes a step of increasing the size of a congestion window in a step-wise manner, wherein the
20 size of the congestion window is step-wise increased to 20% to 100% of the size of the congestion value before start of the handover.

39. Network element according to claim 37, wherein the
25 size of the congestion window is step-wise increased to at least approximately 50% of the size of the congestion value before start of the handover.

40. Network element according to any one of claims 35 to
30 39, wherein the congestion control includes increasing the size of a congestion window in an exponential manner up to a threshold value and a subsequent ramp-like increasing of the congestion window size, wherein the faster recovery rate is implemented by setting the threshold value to at least one-
35 half of, and up to, the previous value of the congestion

window before start of the handover.


41. Network element according to any one of the preceding network element claims, wherein the network element comprises a congestion control means, and wherein when generating or receiving said message, the network element informs its congestion control means which in response triggers the invocation of a fast retransmit and fast recovery algorithm.

10

42. Network element according to any one of claims 35 to 41, wherein the network element comprises a congestion control means, wherein the network element when generating or receiving said message, sends a signal to the congestion control means, the signal indicating to the congestion control means that the congestion control is to be changed so as to provide said faster recovery rate.

43. Network element according to claim 42, wherein the signal is implemented by duplicating ACK packets by an IP layer function to aTCP layer function.

20

**FIG. 1****MOBILE IPv6 BASIC OPERATION**






FIG. 2

**FIG. 3**

**COMPARISON OF BEHAVIOR OF CONGESTION WINDOW
IN RESPONSE TO HANDOVER WITH AND WITHOUT
EMPLOYING EMBODIMENT 1 OF THE INVENTION**

**FIG. 4**

5/8





FIG. 5

**FIG. 6**

**COMPARISON OF BEHAVIOR OF CONGESTION WINDOW
IN RESPONSE TO HANDOVER WITH AND WITHOUT
EMPLOYING EMBODIMENT 2 OF THE INVENTION**





FIG. 7

**FIG. 8**

**COMPARISON OF BEHAVIOR OF CONGESTION WINDOW
IN RESPONSE TO HANDOVER WITH AND WITHOUT
EMPLOYING EMBODIMENT 3 OF THE INVENTION**

INTERNATIONAL SEARCH REPORT

Patent application No
PCT/IB 03/01342**A. CLASSIFICATION OF SUBJECT MATTER**
IPC 7 H04L29/08 H04L1/18

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 7 H04L H04B H04Q

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

INSPEC, EPO-Internal, WPI Data, PAJ

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	CACERES R ET AL: "Improving the performance of reliable transport protocols in mobile computing environments" IEEE JOURNAL ON SELECTED AREAS IN COMMUNICATIONS, JUNE 1995, USA, vol. 13, no. 5, pages 850-857, XP002248963 ISSN: 0733-8716 paragraph [0III] - paragraph [00IV] --- -/--	1-43

☒ Further documents are listed in the continuation of box C.☒ Patent family members are listed in annex.

* Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search

24 July 2003

Date of mailing of the international search report

10. 08. 2003

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax: (+31-70) 340-3016

Authorized officer

FREDRIK BLOMQVIST/MN

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	GOFF T ET AL: "Freeze-TCP: a true end-to-end TCP enhancement mechanism for mobile environments" PROCEEDINGS IEEE INFOCOM 2000. CONFERENCE ON COMPUTER COMMUNICATIONS. NINETEENTH ANNUAL JOINT CONFERENCE OF THE IEEE COMPUTER AND COMMUNICATIONS SOCIETIES (CAT. NO.00CH37064), PROCEEDINGS IEEE INFOCOM 2000. CONFERENCE ON COMPUTER COMMUNICATIONS. NINE, pages 1537-1545 vol.3, XP002248964 2000, Piscataway, NJ, USA, IEEE, USA ISBN: 0-7803-5880-5 paragraph [00II] - paragraph [0III] ---	1-43
A	WO 01 97438 A (NOKIA INC) 20 December 2001 (2001-12-20) page 6, line 14 -page 8, line 28 ---	1-43
A	LIN D ET AL: "TCP fast recovery strategies: analysis and improvements" PROCEEDINGS. IEEE INFOCOM '98, THE CONFERENCE ON COMPUTER COMMUNICATIONS. SEVENTEENTH ANNUAL JOINT CONFERENCE OF THE IEEE COMPUTER AND COMMUNICATIONS SOCIETIES. GATEWAY TO THE 21ST CENTURY (CAT. NO.98CH36169), PROCEEDINGS IEEE INFOCOM'98 CONFERENCE 0, pages 263-271 vol.1, XP002248965 1998, New York, NY, USA, IEEE, USA ISBN: 0-7803-4383-2 paragraph [0004] - paragraph [0005] ---	1-43
A	MISRA A ET AL: "The window distribution of idealized TCP congestion avoidance with variable packet loss" IEEE INFOCOM '99. CONFERENCE ON COMPUTER COMMUNICATIONS. PROCEEDINGS. EIGHTEENTH ANNUAL JOINT CONFERENCE OF THE IEEE COMPUTER AND COMMUNICATIONS SOCIETIES. THE FUTURE IS NOW (CAT. NO.99CH36320), PROCEEDINGS OF INFOCOM'99: CONFERENCE ON COMPUTER COMMU, pages 1564-1572 vol.3, XP002248966 1999, Piscataway, NJ, USA, IEEE, USA ISBN: 0-7803-5417-6 abstract ---	1-43
A	EP 0 991 244 A (NORTEL NETWORKS CORP) 5 April 2000 (2000-04-05) paragraph [0012] -----	1-43

INTERNATIONAL SEARCH REPORT

PCT/IB 03/01342

Patent document cited in search report		Publication date	Patent family member(s)	Publication date
WO 0197438	A	20-12-2001	AU 6987101 A EP 1295428 A2 WO 0197438 A2	24-12-2001 26-03-2003 20-12-2001
EP 0991244	A	05-04-2000	EP 0991244 A2 JP 2000115232 A US 6493316 B1	05-04-2000 21-04-2000 10-12-2002